



## **PRINCIPAL ACTIVITIES**



# DREDGING

## Rio Salado

<b>Where</b>	Buenos Aires, Argentina.
<b>Work</b>	Adequacy of the Salado river Section. 3rd track Sector III
<b>Description</b>	Consisted on the excavations of margins and dredging the riverbed of the Salado River, between survey of 223,918 km to 285,518 km, excavation with backhoes and dredges, and transport to venues for the final disposal of soils.
<b>Amount</b>	58.110.250



## Rio Salado

<b>Where</b>	Buenos Aires, Argentina.
<b>Work</b>	Adequacy of the Salado river Section. 3rd track Sector III
<b>Description</b>	Consisted on the excavations of margins and dredging the riverbed of the Salado River, between survey of 223,918 km to 285,518 km, excavation with backhoes and dredges, and transport to venues for the final disposal of soils.
<b>Amount</b>	40.000.000



## Coaster Ave. Ciudad de Concepción

<b>Where</b>	Entre Ríos, Uruguay.
<b>Work</b>	Construction of Coaster Ave.
<b>Description</b>	Dredging the Uruguay River, a navigable section of the river; and refulado of dredged material for an embankment construction of the on the trace to settle the coastal avenue, refulado a distance of approximately 1,500 meters.
<b>Amount</b>	32.452.315



## ROUTES

### Rural Road improvement

**Where** Córdoba, Argentina.

**Work** Improvement of rural roads. Lot 1.

**Description** It consisted in improving rural roads and aimed to add value to the tertiary road network, on a important production area; for which the following works were executed: land clearing, forest clearing, grubbing, preparing the ground; and construction of compacted fill; granular subbase; and granular base.

**Amount** 7.214.507



### Rural Road improvement

**Where** Córdoba, Argentina.

**Work** Improvement of rural roads. Lot 2.

**Description** It consisted in improving rural roads and aimed to add value to the tertiary road network, on a important production area; for which the following works were executed: land clearing, forest clearing, grubbing, preparing the ground; and construction of compacted fill; granular subbase; and granular base.

**Amount** 2.479.706



### Rural Road improvement

**Where** Córdoba, Argentina.

**Work** Improvement of rural roads. Lot 2.

**Description** It consisted in improving rural roads on dairy areas and aimed to add value to the tertiary road network, on a important production area; for which the following works were executed: land clearing, forest clearing, grubbing, preparing the ground; and construction of compacted fill; granular subbase; and granular base.

**Amount** 2.380.400



## ROCK DRILLING

### Rock Drilling in Claro River

<b>Where</b>	San Luis, Argentina.
<b>Work</b>	Rock Drilling in Claro River.
<b>Description</b>	Rock drilling performance for the foundations treatment; perforations were made rotopercussion, in various diameters, with different inclinations and different depths, in order to perform consolidation injections; waterproofing; and anchors.
<b>Amount</b>	5.546.000



### Rock Drilling in Quinto River

<b>Where</b>	San Luis, Argentina.
<b>Work</b>	Rock Drilling in Quinto River.
<b>Description</b>	Rock drilling performance for the foundations treatment; perforations were made rotopercussion, in various diameters, with different inclinations and different depths, in order to perform consolidation injections; waterproofing; and anchors.
<b>Amount</b>	3.174.000

